

# **Glenisla Golf Course-9 Holer**

## **Summer Goals**

- To maintain and improve overall presentation
- To achieve firmness, trueness and speed without the need to cut too low
- To improve water movement, air content in greens, soil biology, soil nutrition
- Reduce organic matter content through aeration work

## **May;**

Application of fertiliser (Porthcawl) + nitrogen + seaweed + wetting agent

Greens will be cut 7 days

Cutting heights will be 4.5mm, unless specific competitions are to be played

Watering of greens will be done only to maintain moisture levels

## **June;**

Greens will be pencil tined

Application of fertiliser(Porthcawl) + nitrogen + seaweed + wetting agent

Greens will be cut 7 days

Cutting heights will be 4mm

Watering of greens will be done only to maintain moisture levels

## **July;**

Application of fertiliser (Porthcawl) + nitrogen + wetting agent

Greens will be cut 7 days

Cutting heights will be 4mm

Watering of greens will be done only to maintain moisture levels

## **August;**

Greens will be cored, verti cut + top dressed

Application of granule fertiliser + wetting agent

Greens will be cut 7 days

Cutting heights will be 4mm

Watering of greens will be done only to maintain moisture levels

## **September;**

Greens will be pencil tined

Application of fertiliser (Porthcawl) + seaweed + wetting agent

Greens will be cut 7 days

Cutting heights will be 4mm

Watering of greens will be done only to maintain moisture levels

# **Glenisla Golf Course-9 Holer**

## **October:**

Greens will be vertidraind (13mm tine)

Application of fertiliser (Porthcawl) +winter granule + nitrogen + seaweed + wetting agent

## **Weekly Tasks;**

*Tees cut 1 time (8mm)*

*Approach's cut 1/2 times (8mm)*

*Fairways cut 3 times (12/10mm)*

*Semi Rough cut 1 time (44mm)*

## **Bunker;**

*Fully Raked once a week thereafter raked when required*

## **General Maintenance;**

*Strimming all tree bases (4 to 8 weeks)*

*Strimming base of wall at 7<sup>th</sup> & 9<sup>th</sup> (4 to 8 weeks)*

*Strim bank of burn along the 4<sup>th</sup> between the 2 bridges ( 4 to 8 weeks)*

*Pond banks cut every week*